BWDS

Beersheba Wireless Design Solutions
Nad Network Services LLC

QUOTE

Quote No: 10754_TS_ESX_2026
Date: October 29, 2026
Valid for: 30 days
Technician base: Clarksburg, MD

Prepared for: Throne Solution

Professional Wireless Survey Quote — Ekahau SideKick 2 (Active Survey + Full Report)

SCOPE OF WORK

Professional active Wi-Fi site survey at each listed location using Ekahau SideKick 2, performed by an experienced wireless technician, per the client's Statement of Work. The survey documents the current wireless network, AP infrastructure, RF environment, physical site layout, and supporting network infrastructure to enable accurate coverage-remediation and AP planning. On-site work includes: floor-plan verification; ceiling type and height measurement; full AP inventory (count, model, indoor/outdoor, mounting type and height); two photos per AP plus height capture; site-environment and obstacle documentation; IDF/MDF/network-room location and cabling-feasibility assessment with photos; high-density area mapping; Wi-Fi coverage gray-spot analysis with AP-addition feasibility; rogue/unauthorized AP detection; SSID inventory (primary/secondary); wall-type and construction-material survey; client-device count and types; and final annotated floor-plan notes. Active/AP-up survey methodology (RSSI, SNR, 2.4 GHz / 5 GHz).

DELIVERABLES

- Annotated floor plan(s): AP locations, obstacles, high-density areas, coverage gray spots, rogue devices, wall/material types
- Photographic documentation: close-up and wide-angle AP photos, IDF/MDF/network-room photos, obstacle and rogue-device photos/video
- Consolidated AP inventory (model, indoor/outdoor, mounting type/height, operational status, location reference)
- IDF/MDF location log with photos, location details, and cabling-feasibility remarks (also reflected in the Ekahau file)
- Coverage gap (gray-spot) summary with ceiling height and AP-addition feasibility notes
- Rogue / unauthorized AP findings summary with supporting photographs
- SSID and client-device summary (primary/secondary SSIDs, device count and types)
- Completed Ekahau Site Survey project file (.esx) with all annotations, photos, and notes
- Final consolidated survey report formatted as a Word document with supporting photographs and floor plans

PER-SITE PRICING

#	Site	Scheduled Dates	Survey (Full + Report)	Travel & Expenses	Site Total
1	**Phoenix, AZ** 4313 East Cotton Center Blvd, Bldg 8, Allred Cotton Center, Phoenix, AZ 85040-8853	Pending	$3,500	$1,100	$4,600
2	**Aurora, OH** 1515 Danner Drive, Aurora, OH 44202-9273	Nov 2–3	$3,500	$740	$4,240
3	**Milwaukee, WI** 4855 West Electric Avenue, Milwaukee, WI 53219-1628	Pending	$3,500	$950	$4,450
4	**Pewaukee, WI** N16 W22419 Watertown Road, Pewaukee, WI 53186-1118	Nov 16–18	$3,500	$950	$4,450
5	**Florence, SC** 3001 West Radio Drive, Florence, SC 29501-7806	Pending	$3,500	$890	$4,390
6	**Madison, WI** 3030 Ohmeda Drive, Madison, WI 53718-6704	Nov 9–11	$3,500	$950	$4,450
	Subtotals — Survey Labor / Travel & Expenses		**$21,000**	**$5,580**	
	ESTIMATED TOTAL — 6 Sites				**$26,580**

All prices in USD. Survey labor is a flat $3,500 per site (full active survey plus consolidated Word report deliverable); totals are estimates pending floor plans and square footage.

POTENTIAL TRAVEL SAVINGS

Milwaukee and Pewaukee are approximately 20 miles apart — scheduling them in a single trip saves roughly $950 in travel. Combining all three Wisconsin sites (Madison, Milwaukee, Pewaukee) into one trip could save approximately $1,500–$1,800 total.

BWDS

Beersheba Wireless Design Solutions
Nad Network Services LLC

QUOTE

Quote No: 10754_TS_ESX_2026
Date: October 29, 2026
Valid for: 30 days
Technician base: Clarksburg, MD

Prepared for: Throne Solution

ASSUMPTIONS & INCLUSIONS

- Active (AP-up) Ekahau SideKick 2 survey; deliverables include the .esx project file and a consolidated written report in Word format (per the client SOW).
- One on-site day per building assumed for a standard single building up to ~50,000 sq ft; report production is included. Floor plans to be provided before each survey.
- Survey labor: flat $3,500 per site, covering on-site survey, full site documentation (AP inventory, photos, IDF/MDF, rogue-AP scan, SSID and device inventory, wall-material survey) and the consolidated Word report.
- Customer to provide site access, escort if required, and point-of-contact coordination for the survey window.
- All in-scope APs to be powered on (active) and reachable for the duration of the survey.
- Travel & expenses include airfare or mileage, rental car, lodging, and per diem as applicable to each location, billed per the per-site estimates above.

EXCLUSIONS & NOTES

- Pricing assumes up to ~50,000 sq ft per site. Larger or multi-floor sites add approximately $600 per additional 25,000 sq ft.
- This quote covers survey and documentation activities only; it does not include AP installation, configuration, or cabling remediation. Any remediation, replacement, or upgrade recommended as a result of survey findings will be scoped and quoted separately.
- Final pricing confirmed once floor plans and square footage are received.
- Prices in USD. Quote valid 30 days from October 29, 2026.